Scanner enclosure — planning BOM

Currency: RUB Client: _____ Prepared by: _____ Date: _____

Planning estimates only. Replace estimates with supplier quotes. Blank fields require input. Estimated accuracy ±30%.

#	Category	Item	Description	Qty	Unit	Material/unit	Labour/unit	Line total	Supplier	Lead time	Notes
1	Electronics	Raspberry Pi 4 Model B 4GB	Controller board	1	pcs	7,500	0	7,500			estimate
2	Electronics	microSD card 64GB	OS and application storage	1	pcs	1,200	0	1,200			estimate
3	Electronics	Power supply 5V / 3A	Scanner power supply	1	pcs	1,800	0	1,800			estimate
4	Electronics	Powered USB hub, 4 ports	Stable power for four cameras	1	pcs	3,500	0	3,500			estimate; powered hub required
5	Electronics	USB camera 13MP	Capture camera, model TBD	4	pcs	4,500	0	18,000			estimate; model blank
6	Electronics	Touch display 10.1 in	Operator and customer display	1	pcs	12,000	0	12,000			estimate
7	Metal work	Aluminium profile frame 2020	Main frame material	1	set	12,000	6,000	18,000			estimate; cutting and drilling included in labour
8	Metal work	Steel brackets and fasteners	Frame connections	1	set	2,500	0	2,500			estimate
9	Wood work	Plywood base and panels	Base, side panels, internal supports	1	set	4,500	4,500	9,000			estimate; cutting and finishing in labour
10	Glass work	Tempered glass scan surface	Top scanning surface; edge polished	1	pcs	8,000	3,500	11,500			estimate; dimensions blank
11	Lighting	LED strip and diffuser	Scan illumination	1	set	1,800	2,500	4,300			estimate; electrical work in labour
12	Wiring	Wiring, connectors and terminals	Internal electrical harness	1	set	2,500	0	2,500			estimate
13	Cooling	Fan and ventilation grille	Thermal management	1	set	1,500	0	1,500			estimate
14	Finish	Paint and surface consumables	Frame and panel finishing	1	set	2,500	2,500	5,000			estimate
15	Assembly	Mechanical and electrical assembly	Integration of frame, glass, electronics and wiring	1	lot	0	8,000	8,000			estimate
16	Calibration	Testing and calibration	Camera alignment, focus and test scan	1	lot	0	6,000	6,000			estimate
17	Packaging	Packaging	Protective packaging for transport	1	set	1,500	0	1,500			estimate

Cost summary

Item	Value
Material subtotal	80,800 RUB
Labour subtotal	33,000 RUB
Subtotal	113,800 RUB
Overhead (10%)	11,380 RUB
Contingency (5%)	5,690 RUB
Total cost	130,870 RUB
Margin (25%)	32,718 RUB
Price before VAT	163,588 RUB
VAT (20%)	32,718 RUB
Grand total	196,305 RUB

Blank fields: supplier, lead time, client, prepared by, date, revision, part/model numbers, glass dimensions. All prices are planning estimates in RUB; replace with supplier quotes before purchasing.